

VERTICAL ROOF



Includes 6" overhang on all sides

BOXED EAVE ROOF

ALSO KNOWN AS A-FRAME



Includes 6" overhang on all sides



REGULAR ROOF



Includes 6" overhang on front & back

STANDARD FEATURES *Pre-engineered 35PSF-140MPH (3 second gust ultimate wind speed (Vult) 105-120mph / Nominal wind speed 81-93mph)*

Triple Wide carport features include the following: 14 gauge galvanized steel framing, 29 gauge metal roofing with 20 year Beckers paint system, framing spaced 5' on center. On units 12' or taller frame spaces are lowered to 4' on center or less. Includes both peak and leg braces for additional strength and stability. Concrete Anchors & Earth Auger Anchor Package are included in the base price. Eagle Carports, Inc. is not responsible for stopping, or repairing leaks under base rails. Base leg height is 6' tall. Please note: Eagle Carports, Inc. does not provide site work. Customers are required to contact local building/zoning departments about codes for permitting purposes before order finalization.

PRICING SHOWN IS FOR RISK CATEGORY I/WIND EXPOSURE C. PLEASE CALL FOR RISK CATEGORY II OPTIONS.

26x20	28x20	30x20
\$3,595	\$3,795	\$3,995
26x25	28x25	30x25
\$4,395	\$4,595	\$4,795
26x30	28x30	30x30
\$5,095	\$5,395	\$5,695
26x35	28x35	30x35
\$5,895	\$6,195	\$6,495
26x40	28x40	30x40
\$6,695	\$6,995	\$7,295
26x45	28x45	30x45
\$7,495	\$7,745	\$7,995
26x50	28x50	30x50
\$7,695	\$7,945	\$8,395

All base units include standard 6' legs (eave height).

26x20	28x20	30x20
\$2,895	\$3,045	\$3,195
26x25	28x25	30x25
\$3,495	\$3,645	\$3,795
26x30	28x30	30x30
\$3,995	\$4,195	\$4,395
26x35	28x35	30x35
\$4,595	\$4,845	\$5,095

26x20	28x20	30x20
\$2,795	\$2,945	\$3,095
26x25	28x25	30x25
\$3,395	\$3,545	\$3,695
26x30	28x30	30x30
\$3,895	\$4,095	\$4,295
26x35	28x35	30x35
\$4,495	\$4,695	\$4,895



29 GAUGE SHEET METAL SPECS:
ASTM A653 Grade 80
G40 Galvanized Coating or AZ40
20-Year Beckers Paint System

TUBE FRAME SPECS:
ASTM A653 HSLA Grade 50
G60 Galvanized Coating
14 Gauge Steel / Optional 12 Gauge



- ✓ **FREE EAGLE EMBLEM!**
- ✓ **FINANCING & RTO AVAILABLE!**
- ✓ **90 DAY WORKMANSHIP WARRANTY!**
- ✓ **INSTALLATION INCLUDED!** (Restrictions apply)

- Lot must be cleared & leveled prior to installation.
- All cement pads must have turn down footers.
- Price doesn't include site preparation.



OPTIONAL FEATURES FOR 26' - 30' WIDE CARPORTS - REF. # 24147S

Prices effective 11.08.2024

OPTIONAL 12G FRAME UPGRADE		20'L	25'L	30'L	35'L	40'L	45'L	50'L
26' - 30' w (6'-11' Tall)		\$1,110	\$1,270	\$1,430	\$1,590	\$1,750	\$1,910	\$2,070
26' - 30' w (12'-16' Tall)		\$1,665	\$1,905	\$2,145	\$2,385	\$2,625	\$2,865	\$3,105
FLUSH MOUNT KIT		\$200	\$220	\$240	\$260	\$280	\$300	\$320

Flush mount kits allow cement pads to be the exact width and length of the building without requiring a 2" perimeter.

EAVE / LEG HEIGHT	HEIGHT	20'L	25'L	30'L	35'L	40'L	45'L	50'L
	7'	\$80	\$100	\$120	\$140	\$160	\$180	\$200
	8'	\$160	\$200	\$240	\$280	\$320	\$360	\$400
	9'	\$240	\$300	\$360	\$420	\$480	\$540	\$600
	10' Reinforced Legs*	\$600	\$750	\$900	\$1,050	\$1,200	\$1,350	\$1,500
	11' Reinforced Legs*	\$700	\$850	\$1,000	\$1,150	\$1,300	\$1,450	\$1,600
	12' Double Legs **	\$1,250	\$1,600	\$1,800	\$2,000	\$2,200	\$2,550	\$2,750
	13' Double Legs **	\$1,350	\$1,700	\$1,900	\$2,100	\$2,300	\$2,650	\$2,850
	14' Double Legs **	\$1,450	\$1,800	\$2,000	\$2,200	\$2,400	\$2,750	\$2,950
	15' Double Legs **	\$1,650	\$2,000	\$2,200	\$2,400	\$2,600	\$2,950	\$3,150
	16' Double Legs **	\$1,850	\$2,200	\$2,400	\$2,600	\$2,800	\$3,150	\$3,350

** Please note rafter spaces has been reduced from the standard 5' on center to 4' on center or less.

CLOSE BOTH SIDES	HEIGHT	20'L	25'L	30'L	35'L	40'L	45'L	50'L
	6'	\$550	\$650	\$750	\$850	\$950	\$1,050	\$1,150
	7'	\$675	\$800	\$925	\$1,050	\$1,175	\$1,300	\$1,425
	8'	\$750	\$900	\$1,050	\$1,200	\$1,350	\$1,500	\$1,650
	9'	\$810	\$975	\$1,140	\$1,300	\$1,465	\$1,625	\$1,790
	10'	\$875	\$1,050	\$1,225	\$1,400	\$1,575	\$1,750	\$1,925
	11'	\$975	\$1,175	\$1,375	\$1,575	\$1,775	\$1,975	\$2,175
	12'	\$1,035	\$1,250	\$1,465	\$1,675	\$1,890	\$2,100	\$2,315
	13'	\$1,100	\$1,325	\$1,550	\$1,775	\$2,000	\$2,225	\$2,450
	14'	\$1,280	\$1,530	\$1,780	\$2,030	\$2,280	\$2,530	\$2,780
	15' Vertical	\$1,950	\$2,360	\$2,770	\$3,180	\$3,590	\$4,000	\$4,410
	16' Vertical	\$2,000	\$2,410	\$2,820	\$3,230	\$3,640	\$4,050	\$4,460

VERT. SIDES	V. WAINSCOTING	\$320	\$400	\$480	\$560	\$640	\$720	\$800
-------------	----------------	-------	-------	-------	-------	-------	-------	-------

CLOSE ONE END Per End	HEIGHT	26'W	28'W	30'W
	6'	\$1,050	\$1,125	\$1,200
	7'	\$1,200	\$1,300	\$1,400
	8'	\$1,250	\$1,350	\$1,450
	9'	\$1,300	\$1,400	\$1,500
	10' Reinforced Legs*	\$1,600	\$1,725	\$1,850
	11' Reinforced Legs*	\$1,650	\$1,775	\$1,900
	12' Double Legs **	\$1,775	\$1,925	\$2,075
	13' Double Legs **	\$1,850	\$2,000	\$2,150
	14' Double Legs **	\$1,900	\$2,050	\$2,200
	15' Double Legs **	\$2,405	\$2,590	\$2,775
	16' Double Legs **	\$2,510	\$2,705	\$2,900
	6'-8'	\$350	\$375	\$400
	9'-12'	\$375	\$400	\$425
	13'-14'	\$400	\$425	\$450
	V. WAINSCOTING Per End	\$390	\$420	\$450

Vertical sides and ends must have vertical roof style

CONCRETE DIMENSIONS All stated dimensions are in reference to the frame size, not the roof dimensions.

With Flush Mount Kit

Cement pads do not require additional width.

Ex. 20' x 30' unit will need a 20' x 30' pad.

Without Flush Mount Kit

All cement pads require 2" wider on all sides.

Ex. 20' x 30' unit will need a 20'4" x 30'4" pad.



EXTRA PANELS

LENGTH PRICE *J-TRIM

20'	\$120	Add \$75
25'	\$140	Add \$90
30'	\$160	Add \$105
**35'	\$180	Add \$120
**40'	\$205	Add \$135
**45'	\$230	Add \$150
**50'	\$255	Add \$165

*J-Trim price covers both sides **Not a continuous panel

WALK-IN DOORS - 36"X80"

MHD:Right H. Outswing | RD: Right H. Inswing

24"x36" 30"x36"

MOBILE HOME DOOR \$395

\$195

9 LIGHT STEEL DOOR \$575*

\$215

*Special Order item. ONLY available to install on cement.

GABLE ON END Priced Per End

For Vertical Gable multiply price by 1.5. For Extended Horizontal Gable multiply by 2. For Extended Vertical Gable multiply by 3.

26'W 28'W 30'W

\$425 EA.

\$475 EA.

\$525 EA.

*Extended Gables have an additional 3' of coverage.

TRIMMED HALF PANELS 12' - 30'

Kit made for both sides. Package price cannot be halved.

20'L 25'L 30'L 35'L 40'L 45'L 50'L

\$200

\$225

\$250

\$275

\$400

\$425

\$450

CORNER KIT Must add Gable

Legs 6'- 8' \$225

Legs 9'- 12' \$375

Legs 13'- 16' \$525

FRAME OUTS

Use for framing of customer provided windows & doors

WINDOW WALK-IN DOOR

\$70

\$85

STANDARD HEADERS / LARGE OPENINGS UNITS 12' - 30'

OPENINGS ON THE SIDE

OPENING 6-11' WIDE \$150

OPENING 6-14' WIDE \$150

OPENING 12-16' WIDE \$300

OPENING 15' WIDE \$300

OPENING 16' WIDE \$400

OPENING 16' WIDE \$400

*Side must be 1' taller than desired door height. 14'x14' requires 2 foot taller.

Must include with garage door purchase.

HORIZONTAL WAINSCOTING

Not available on 6' tall buildings.

Price is \$4/ft x Perimeter on buildings with 10' and 7' eaves.

EXTRA RAFTERS/ BOWS

26' - 30'W

\$250 EA.

6' standard incl. \$20 per foot up to 14' tall.

INSULATION

DOUBLE BUBBLE TYPE (MOISTURE BARRIER)

R5

\$1.50 SF

2" FIBERGLASS

R7

\$2.25 SF

ROOF (Vertical Only): Add 2' to width and multiply by length. Ex. 24' wide x 26' long 26 x 26 = 676 SF x \$/per SF

SIDES: Multiply leg height by length by 2. Ex. 26' long x 10' tall 10 x 26 = 260 sf x \$/per SF

ENDS: Add 1.5 to leg height, multiply by building width. Ex. 24' wide x 10' tall 11.5 x 24 = 276 x 2 = 552 sf x \$/per SF

ADDITIONAL LABOR FEES

20'L 25'L 30'L 35'L 40'L 45'L 50'L

BUILD OVER FEE \$150

\$175

CUT LEGS ON SITE* \$100

\$125

\$150

\$175

\$200

\$225

\$250

\$350

*Cut leg fee has a maximum of 12" adjustment possible, either front to back or side to side.

Please note, side to side on level lots will result in gap underneath garage doors.